



NOTE:

1. AN 18"-24" WIDE PAVEMENT REPAIR STRIP SHALL BE CONSTRUCTED ALONG PROPOSED CURB. THE FOLLOWING ITEMS OF WORK ARE INCLUDED UNDER 9"x20" CONCRETE VERTICAL CURB:
 - SAWCUT
 - CONCRETE CURING AND SEALING COMPOUND
 - BACKFILL MATERIAL
 - COMPACTED SUBGRADE
 - REMOVAL OF MONOLITHIC CONCRETE CURB AND GUTTER (IF REQUIRED)
2. IF TOPSOILING, 4" THICK, FERTILIZING AND SEEDING, TYPE A-3 AND STRAW MULCHING ARE SEPARATE PAY ITEMS.
3. FULL CURB DEPTH SHALL BE MAINTAINED AT DROP CURBS. EXPANSION JOINTS ARE REQUIRED EVERY 10' AND PER DROP CURB DETAIL.
4. 4" THICK, COARSE AGGREGATE SIZE NO. 57 SHALL BE CONSTRUCTED UNDER PROPOSED CURB IN WET FIELD CONDITIONS AS DIRECTED BY ENGINEER.
5. TOP OF CURB SHALL NOT BE SET HIGHER THAN ADJACENT EXISTING OR PROPOSED SIDEWALK UNDER ANY CONDITION



Bergen County Department of
Planning and Engineering

**9" x 20" CONCRETE
VERTICAL CURB**

NOT TO SCALE

10/2024